

***NIH Computer Center  
Disaster Recovery Plan***

*April 2004*



## **FOREWARD**

This Disaster Recovery Plan describes the strategy and procedures for recovering Data Center processing of critical applications should a disaster substantially disrupt operations.

The plan is organized into three parts: the main body provides a general description of the disaster recovery strategy and program, the appendices provide detailed information for conducting the recovery, and the attachments provide supplemental information. The main body is public information and may be freely distributed; the appendices and attachments contain sensitive information that is restricted to the individuals responsible for recovering Data Center operations. The appendices and attachments must be destroyed when updated versions are received.

The plan is frequently updated to reflect current hardware, software, procedures, critical applications, and staffing. Revisions are distributed to the disaster recovery team members at least twice a year following the disaster recovery tests.

When copies of the plan are no longer required, please return them to the Disaster Recovery (DR) Coordinator. All corrections are welcome at any time and should be directed to the DR Coordinator.

Adrienne Yang  
Disaster Recovery Coordinator



**TABLE OF CONTENTS**

**1 INTRODUCTION..... 1-1**

1.1 PURPOSE ..... 1-1

1.2 SCOPE ..... 1-1

1.3 DISASTER RECOVERY STRATEGY..... 1-2

1.4 DISASTER DEFINITION ..... 1-3

1.5 ASSUMPTIONS ..... 1-3

1.6 CONTRACTUAL ARRANGEMENT FOR RECOVERY SERVICES..... 1-4

**2 DISASTER RECOVERY ACTION PLAN..... 2-1**

2.1 BACKUP AND OFF-SITE STORAGE PROCEDURES ..... 2-1

2.2 OFF-SITE STORAGE SERVICES..... 2-1

2.3 DISASTER RESPONSE..... 2-1

2.4 HOT SITE HARDWARE AND SOFTWARE CONFIGURATIONS..... 2-2

2.5 RESUMING NORMAL OPERATIONS ..... 2-4

2.6 SECURITY..... 2-4

**3 FUNCTIONAL TEAMS AND RESPONSIBILITIES ..... 3-1**

3.1 DAMAGE ASSESSMENT TEAM ..... 3-1

3.2 EXECUTIVE TEAM ..... 3-1

3.3 RESTORATION TEAM..... 3-2

3.4 OPERATIONS TEAM ..... 3-2

3.5 CUSTOMER SUPPORT TEAM ..... 3-3

3.6 SALVAGE/RECLAMATION TEAM ..... 3-3

3.7 ADMINISTRATIVE SUPPORT TEAM ..... 3-4

**4 TESTING THE DISASTER RECOVERY PLAN..... 4-1**

4.1 HOT SITE TEST PROCEDURES ..... 4-1

4.2 HOT SITE TEST PLANNING ..... 4-1

4.3 SUPPORT FOR CRITICAL APPLICATION TESTING..... 4-2

4.4 POST-TEST WRAP-UP ..... 4-2

4.5 HOT SITE TEST SCHEDULE ..... 4-3

4.6 PLAN REVIEWS AND TRAINING ..... 4-4

**5 MAINTAINING THE PLAN..... 5-1**

**APPENDICES**

- Appendix A: Critical Applications and Contact Information
- Appendix B: Directions to Work Area Recovery Center
- Appendix C: Disaster Alert Procedures, Team Members, and Contact Information
- Appendix D: Hot Site Contact Information and Procedures
- Appendix E: Off-Site Storage Contact Information and Emergency Procedures
- Appendix F: Restore Procedures
- Appendix G: Data Communications Architecture and Configuration

- Appendix H: Vendor Contacts
- Appendix I: Contents of the Documentation Box (Doc Box)
- Appendix J: Guidelines for Application Hot Site Tests
- Appendix K: VTAM Telecommunications

**ATTACHMENTS**

- Attachment 1: Backup Listings
- Attachment 2: Calendars with Julian Dates
- Attachment 3: Hot Site Contract
- Attachment 4: 3172 Configuration Controls
- Attachment 5: Disaster Recovery Communication Topology
- Attachment 6: Hot Site Tests Technical Assistance Packages (TAPs)
- Attachment 7: Hot Site Test Plans and Reports
- Attachment 8: Contents of Hot Site Storage Lockers
- Attachment 9: Instructions for Completing FedEx Labels
- Attachment 10: OS/390 Hardware Configuration
- Attachment 11: Department of the Treasury Payment File Contingency Procedures

## 1 Introduction

The Center for Information Technology (CIT) at the National Institutes of Health (NIH) provides information processing services to NIH research and management programs, as well to Department of Health and Human Services (DHHS) and other government agency management programs. CIT also provides networking and telecommunications services to NIH. The information technology equipment supporting these services is housed in the NIH Data Center (the *Data Center*) which is operated by the Division of Computer System Services (DCSS), a component of CIT.

In March 1992 a formal Business Impact Analysis (BIA) of the Data Center's major applications was completed. The resulting disaster recovery plan to mitigate extended interruptions focused on the mainframe, since the major applications were hosted on that platform. Over time, critical applications were being hosted on UNIX systems and the disaster recovery plan was expanded to include those systems.

Since DCSS is an information technology service provider, DCSS offers the Disaster Recovery Program as a service. It is incumbent upon customers to designate their applications as critical for inclusion in the Disaster Recovery Program.

### 1.1 Purpose

This Disaster Recovery Plan documents CIT's Disaster Recovery Program for recovering limited Data Center operations after a disaster. The plan describes the preparation and actions required to effectively respond to a disaster, assigns responsibilities, and describes the procedures for testing and maintaining the plan.

### 1.2 Scope

The Disaster Recovery Plan is focused only on those DCSS-owned and managed computer systems that host critical applications, currently the OS/390 mainframe system, Titan, and the UNIX platforms comprising the EOS system. This plan addresses all preparation and steps necessary to restore processing on those systems so that the critical applications can continue processing after a disaster has rendered any or all of the systems inoperable.

Many functions and facilities that would be needed in a disaster involving physical devastation are outside the current scope of this plan. These include, but are not limited to:

- care for affected CIT personnel and their families;
- communications equipment supporting the NIH network (NIHnet) and the equipment supporting the NIH electronic mail services;
- computing equipment owned by other entities that is housed in the Data Center;

- voice communications internal to CIT;
- ongoing communications protocol between the CIT and NIH officials outside of CIT;
- the role of non-CIT NIH officials following a disaster;
- handling inquiries from the Press;
- implementation of controls to prevent disasters; and
- other aspects of contingency planning such as responses to various localized system outages.

### 1.3 Disaster Recovery Strategy

Should the Data Center encounter a disaster that prevents it from functioning, DCSS is prepared to provide adequate computational, data storage, and data communications services and facilities at an off-site disaster recovery resource for the designated critical applications. The off-site disaster recovery resource is a fully operational data center that is prepared to host the NIH systems and critical applications; it is referred to as the *hot site*.

Customers are responsible for disaster recovery preparedness for their applications in the event of a disaster. There is no mandatory requirement that critical applications use the Data Center's disaster recovery services and facilities. Application owners are free to make other disaster recovery arrangements.

DCSS has assigned a Disaster Recovery Coordinator to oversee the Disaster Recovery Program. The Disaster Recovery Coordinator is responsible for:

- periodically surveying program managers from the customer community to determine which applications require disaster recovery services and/or resources;
- organizing regularly-scheduled, periodic tests of the disaster recovery procedures;
- maintaining and updating the Disaster Recovery Plan based on changes in customer requirements, personnel, hardware and software configurations, and the results of disaster recovery tests and plan reviews; and
- orchestrating the execution of the Disaster Recovery Plan when a disaster has been declared.

DCSS has also designated a Disaster Recovery Technical Support Coordinator for each of the processing systems covered by this Disaster Recovery Program. The coordinators are responsible for:

- assisting the critical application customers in preparing for the disaster recovery test events;

- serving as liaisons for the critical application customers during the disaster recovery tests (by assisting customers in resolving errors in jobs, reporting communications problems to the DCSS disaster recovery team, and answering disaster recovery testing questions in general); and
- assisting the critical application customers in preparing their applications to run successfully at the hot site in the event of a disaster.

DCSS is ready to work with application program managers and technical leaders to further the disaster recovery capabilities of the critical applications. However, it is important that managers of critical applications participating in the Data Center's Disaster Recovery Program pro-actively prepare their applications for a disaster. This includes participating in the periodic hot site tests and communicating with the Data Center's Disaster Recovery Coordinator regarding significant changes or developments in their applications.

## **1.4 Disaster Definition**

For the purposes of this plan, a disaster is any unplanned event that prevents the Data Center from providing services needed by the designated critical applications for a period of 72 hours or longer. Conditions that could be declared a disaster include, but are not limited to, extended electrical power outage to the computer room, and fire, smoke, water, or explosion damage to computing equipment.

In the event of a disaster, the Damage Assessment Team (reference Section 3.1) will evaluate the damage to the physical assets and functional capability of the Data Center, and report its findings to the Executive Team (reference Section 3.2). The Executive Team will consider the findings together with other available information to make a decision regarding a formal disaster declaration. Only the Executive Team has the authority to declare a disaster.

## **1.5 Assumptions**

The Disaster Recovery Plan has been developed under the following assumptions:

- Only the Data Center is damaged; other buildings on the NIH campus are unaffected.
- Only those applications (listed in Appendix A) that are currently designated as critical will be supported.
- A disaster will result in real losses, both for the Data Center itself, and for many of the applications that it supports. At a minimum, time, money, and operational capability will be lost. A physical disaster (hurricane, flood, bomb, etc.) would lead to the loss of at least some data and software.

## **1.6 Contractual Arrangement For Recovery Services**

CIT has an Inter-Agency Agreement with the General Services Agency (GSA) for hot site services to accommodate recovery of critical applications for the Titan and EOS systems.

## **2 Disaster Recovery Action Plan**

### **2.1 Backup and Off-Site Storage Procedures**

#### ***Titan:***

All disks are dumped to tape on weekly cycles. These weekly dumps are written simultaneously to two separate automated tape libraries (ATLs), one located in the Data Center and the second located in another HHS agency computer center outside Baltimore, Maryland. The latter set of tapes are referred to as the *off-site backup tapes*. Both backups are cycled through six sets of tapes so that six successive weeks worth of backups are always maintained.

#### ***EOS:***

EOS system disks are dumped to tape on weekly cycles and the tapes are rotated to a secure off-site storage facility. The off-site backup tapes are cycled through six sets of tapes. Customer files and data are included in the dumps for those customers who have requested off-site disaster data storage.

### **2.2 Off-Site Storage Services**

CIT has contracted with a commercial vendor to provide secure off-site storage services. The vendor's facility and procedures meet Department of Defense standards for secure storage. The following services are provided under CIT's contract:

- Delivery of the backup tapes between the storage facility and the Data Center on a weekly schedule;
- Delivery of backup tapes (both those stored at the storage facility and at the NIH campus) to the hot site upon request and as directed by the Data Center (both for disaster recovery tests and for an actual disaster); and
- Delivery of the backup tapes from the hot site back to NIH.

In general, the vendor can respond within two hours notice, twenty-four hours per day, three hundred sixty-five days per year.

### **2.3 Disaster Response**

In the event of a disaster, DCSS will take the following actions; responsible teams are indicated:

- Assess the damage to the Data Center to determine if a disaster should be declared. (Damage Assessment Team)
- Make the decision to formally declare a disaster. (Executive Team)

- Establish a Disaster Command Post, if necessary, in another building on the NIH campus having appropriate communications and support equipment. (Executive Team)
- Notify the off-site storage facility, the hot site, key NIH executives, and the critical application sponsors of the disaster declaration. (Executive Team)
- Work with the hot site staff to restore the NIH operating systems and applications at the hot site and establish the communications link to the hot site in preparation for operating at the hot site for the duration of the emergency. (Restoration Team, Operations Team, and Customer Support Team)
- Reconstruct the Data Center. (Salvage/Reclamation Team)
- Conduct operations at the hot site until the Data Center is ready to resume operations. (Operations Team, Restoration Team, and Customer Support Team)
- Conduct preparations to leave the hot site and to resume operations at the Data Center. (Operations Team and Restoration Team)

Reference Section 3, Functional Teams and Responsibilities, for details regarding the responsibilities of the disaster recovery teams and the actions required to accomplish the above listed tasks.

## **2.4 Hot Site Hardware and Software Configurations**

The Data Center's standard disaster recovery configuration at the hot site includes a mainframe system, UNIX systems, data communications support to the mainframe and UNIX systems, and a work area recovery center.

The following are the major hardware components of the standard mainframe configuration:

- IBM processor with sufficient MIPS and memory capacity,
- two logical partitions (LPARs),
- sufficient quantity of tape drives (STK 9840, 3490-B40, 3480-B22, and 3420-8),
- sufficient disk storage (3390-3 DASD), and
- sufficient printer capacity (4245-20 impact printers, 3900 printer, and 3287-2 printer).

The following system software and subsystems will be loaded into the hot site mainframe LPARS as appropriate:

- OS/390 operating system,
- Resource Access Control Facility (RACF),
- TSO/ISPF,
- Wylbur under TSO,
- Customer Information Control System (CICS),

- Job Control Language (JCL),
- ADABAS,
- NATURAL,
- MODEL 204,
- SPF,
- Transport Control Protocol/Internet Protocol (TCP/IP – TN3270),
- File Transfer Protocol (FTP),
- SAS,
- IMS,
- VISION:Builder and VISION:Report, and
- CONNECT:Direct.

The following are the major hardware components of the standard UNIX configuration:

- AlphaServer 8400 5/625 with sufficient memory capacity,
  - sufficient internal and external disk storage,
  - CD ROM drive,
  - sufficient quantity of tape drives,
  - Laser Jet printer, and
  - network connectivity.
- Sun E450 UltraSPARC server with sufficient memory capacity,
  - sufficient internal and external disk storage,
  - CD ROM drive,
  - tape drive, and
  - network connectivity.

The following system software will be loaded onto the hot site AlphaServer:

- Tru64 Operating System,
- Oracle relational database management system,
- CONNECT:Direct, and
- ADSM.

The following system software will be loaded onto the hot site UltraSPARC server:

- Solaris Operating System, and
- Oracle relational database management system.

Note that at the hot site, the functions of multiple AlphaServers and multiple UltraSparc servers are consolidated into one machine, respectively.

The following are provided to support data communications to the hot site:

- Network Control Center for communication support to the mainframe and UNIX computers,
- Front End Processor for communications support to the mainframe,
- remote console support for the UNIX computers, and
- dedicated T1 line with appropriate routers for IP communication between Washington, D.C., and the mainframe and UNIX computers.

The following are the provisions at the work area recovery center, located within driving distance of the Washington, D.C. metropolitan area:

- enough work space to accommodate thirty-two (32) individuals,
- twenty-five work stations,
- twenty-five phone sets,
- twenty-five 3270 display stations,
- remote consoles for the UNIX computers,
- ethernet connection to the hot site, and
- one facsimile machine and one copier.

DCSS will contract for additional emergency hot site support to meet individual customer's special needs.

## **2.5 Resuming Normal Operations**

While recovery operations are ongoing at the hot site, the Salvage/Reclamation Team will be managing the restoration or rebuilding of the Data Center. The decision regarding the order of restoring applications on the systems at the Data Center will be made just prior to resuming operations at the Data Center. It may be beneficial to install non-critical applications first in order to test Data Center operations before the critical applications are installed.

## **2.6 Security**

While operating at the hot site, information security will be assured by the security controls on the hot site host systems which will be configured in accordance with the policies and procedures governing the security of the Titan and EOS systems. As processing continues at the hot site, the hot site host systems will be closely monitored to ensure the systems are not compromised.

### **3 Functional Teams and Responsibilities**

The following subsections describe each functional team's role as well as its responsibilities in preparing for and responding to a disaster. The responsibility for planning, coordinating, and managing this program is assigned to the Disaster Recovery Coordinator with assistance from technical advisors.

The appendices and attachments provide supplemental information and instructions to assist the teams in fulfilling their functions.

#### **3.1 Damage Assessment Team**

The Damage Assessment Team assesses the extent of the damage to the Data Center, reports to the Executive Team, and makes a recommendation on declaring a disaster.

The major pre-disaster responsibility is to determine appropriate considerations/criteria for identifying the extent of the damage and the estimated duration of the outage.

The disaster responsibilities and actions are:

- Receive the first alert regarding the disaster.
- Ensure that the NIH police/fire departments have been notified.
- Coordinate with the police and/or fire department to provide for safety, security, and access to the damaged facility.
- Notify the DCSS Director or alternate regarding the potential disaster.
- Assess the damage to each area of the computer facility.
- Brief the Director or alternate, communicating the recommendation(s).

#### **3.2 Executive Team**

The Executive Team officially declares that a disaster has occurred, authorizes the execution of the Disaster Recovery Plan, and oversees the execution of the plan during the emergency.

The pre-disaster responsibilities are:

- Approve the DCSS Disaster Recovery Plan and all major or material modifications to the plan.
- Establish primary and alternate disaster command posts, ensuring that the posts are adequately prepared for a disaster.

The disaster responsibilities and actions are:

- Notify the hot site and the off-site storage facility of a possible disaster.
- Review the report of the Damage Assessment Team.

- Declare a disaster:
  - a) establish the command post and communications,
  - b) activate the Functional Teams,
  - c) inform the hot site of the disaster declaration, and
  - d) initiate the shipment of the backup materials to the hot site.
- Notify the Key Executives (listed in Appendix C).
- Monitor the performance of the Disaster Recovery Teams and the execution and effectiveness of the Disaster Recovery Plan.
- Keep senior CIT management and the designated Information Officer/alternate informed of material/sensitive matters.

### **3.3 Restoration Team**

The Restoration Team brings the hot site systems to operational mode by managing the relocation of services to the hot site, initiating and managing the recovery procedures at the hot site, and responding to operational problems at the hot site. The Restoration Team also manages the relocation of services back to the Data Center.

The pre-disaster responsibilities are:

- Establish and maintain the recovery procedures for the hot site systems.
- Manage and maintain the backup procedures.
- Establish and maintain the disaster recovery data communications link.
- Plan and conduct regular hot site tests.

The disaster responsibilities and actions are:

- Coordinate recovery procedures with hot site personnel.
- Restore the operating systems environments on the hot site host systems.
- Establish the data communications link to the hot site.
- Verify the operating systems and all other system and communication software are working properly.
- Restore the designated critical application files.
- Support the operations at the hot site by resolving problems and monitoring and maintaining the data communications link to the hot site.
- Manage the backup tapes that were sent to the hot site.
- Ensure all required backups of the entire system are completed in preparation for leaving the hot site.
- Coordinate the return of the DCSS/customer media to the Data Center.
- Install all NIH system software at the Data Center.

### **3.4 Operations Team**

The Operations Team assists in the recovery operations and manages the operations of the computer systems at the hot site.

The pre-disaster responsibilities are:

- Ensure that appropriate backups are made on the prescribed, rotating basis and are ready to be taken off-site.
- Maintain current, up-to-date systems operations documentation, ensuring that this documentation is in the doc box, and, as needed, is stored suitably at the off-site storage facility.

The disaster responsibilities and actions are:

- Provide assistance to the Restoration Team in the restoration of the system software and customer files, as required.
- Run system and operation jobs, as required.
- Implement and maintain a problem log.
- Provide information to the Customer Support Team regarding the status of the system, operations, and the customer jobs.
- Effect the transfer of critical media and print output from the hot site to suitable customer pickup location(s).
- Coordinate the shutdown of the hot site operations and the transfer back to the Data Center.

### **3.5 Customer Support Team**

The Customer Support team provides assistance to customers during the disaster from the time the disaster is declared until operations resume at the Data Center.

The pre-disaster responsibilities are:

- Advise and consult with critical application customers regarding their disaster recovery requirements.
- Assist critical application customers during disaster recovery tests.

The disaster responsibilities and actions are:

- Notify critical application customers that a disaster has been declared.
- Advise customers of the disaster recovery system status, availability, and accessibility.
- Provide problem diagnosis and resolution guidance/assistance to application owners and their customers.

### **3.6 Salvage/Reclamation Team**

The Salvage/Reclamation Team manages the restoration or rebuilding of the Data Center.

The major pre-disaster responsibility is to maintain current copies of equipment inventory lists, physical plant layout/diagrams (floor plans), and other pertinent documentation describing the DCSS production hardware configuration in the doc box.

The disaster responsibilities and actions are:

- After the Restoration Team has implemented recovery operations at the hot site, assess the damage to the Data Center and report the damage, with recommendations, to the Executive Team.
- Organize the recovery of salvageable equipment, supplies and the physical plant.
- Initiate, coordinate, and expedite construction and work requests to prepare the NIH facility to receive equipment, supplies, tools, machinery, and utilities (electrical power, telephones, network connectivity, air conditioning, plumbing, water, gas, and HVAC).
- Order and expedite replacements for unusable IT equipment.
- Monitor the construction of the new/repared facility, and the installation of all utilities and other essentials.
- Monitor the installation of computers, peripherals, and other IT equipment.
- Advise the Executive Team regarding status, progress, and schedules, and any problems associated with the construction/reconstruction and installation.
- Inform the Executive Team when the new/restored facility is ready for use by the critical applications and by other customers.

### **3.7 Administrative Support Team**

The Administrative Support Team provides logistical and organizational support for all the other teams.

The major pre-disaster responsibility is to prepare up-to-date property management lists, inventory lists, and other pertinent documentation on the physical assets of the Data Center, ensuring current copies of this documentation are in the doc box.

The disaster responsibilities and actions are:

- Prepare travel orders and other documents to facilitate the Restore Team activities.
- Provide general administrative support to the Executive Team and to all other DCSS Functional Teams, as necessary.

## 4 Testing the Disaster Recovery Plan

Testing and exercising the Disaster Recovery Plan helps to verify that the recovery procedures work as intended and that the supporting documentation is accurate and current. Testing also provides an opportunity to identify any omissions in recovery procedures or documentation and to determine whether personnel are adequately prepared to perform their assigned duties. Therefore, DCSS regularly schedules exercises of its Disaster Recovery Plan at the vendor hot site, referred to as hot site tests (HSTs).

### 4.1 Hot Site Test Procedures

DCSS schedules the hot site tests for a two day period, covering the disaster recovery procedures for both Titan and EOS. The first day is dedicated to exercising the system recovery procedures and establishing the communications link. The second day is dedicated to testing the recovery of critical applications. The hot site tests are managed and conducted by members of the Restoration Team, the Operations Team, and the Customer Support Team, referred to collectively as the *HST Team*.

Prior to the HSTs, the HST Team determines which backup tapes will be used for the tests, establishes a test plan which outlines the goals and activities for the given HST, conducts the necessary preparations for the test, and assists customers in their preparations for the HST. During the tests, in addition to providing customer assistance, the HST Team participants maintain a running log of the test activities to assist in the post-test review.

After every test, the HST Team participants meet to discuss the tests in order to improve the recovery procedures and the plan documentation. The HST Team also schedules a meeting with the customers to gain their input and suggestions for improvements.

### 4.2 Hot Site Test Planning

To ensure a successful hot site test, the HST team will:

- Confirm with the hot site vendor that the hot site mainframe, UNIX computer, and data communications configurations will meet the HST needs, and that the hot site will be ready for the test. (Two to three months prior to the scheduled test)
- Set the objectives for the test and establish action items for the team in preparation for the test. (At least two months prior to the scheduled test)
- Disseminate information to the user community regarding the test. (Six to eight weeks prior to the scheduled test)
- Confirm that preparatory tasks are being completed and review the schedule of events for the days of the HST. (Four to six weeks prior to the scheduled test)

- Discuss the final test preparations with the hot site vendor to confirm the hot site configurations, to obtain the information required for the mainframe backups, and to reconfirm the hot site will be ready. (Two to three days before the scheduled backups for the test will be taken)
- Send the backup tapes and tape lists to the hot site. (One week prior to the scheduled test)

Reference Appendix J for complete guidelines and instructions for preparing and testing applications during a hot site test. This guideline is distributed to the user community well in advance of the HST.

### **4.3 Support for Critical Application Testing**

The HST Team offers user support during a hot site test to assist the application owners/participants in successfully running their applications at the alternate site. The assistance includes help with test preparations, on-call support during the duration of the test, resolving reported problems, and serving as the liaison between the user and the HST Team.

Test preparation support includes:

- Ensuring the users have made all appropriate preparations for their data to be available for the HST (this includes particularly, WYLBUR profiles, TSO CLISTS, ISPF profiles for Titan),
- Ensuring the users are ready for the HST and have no further questions, and
- Ensuring users have the necessary contact phone numbers for user support during the HST.

Hot site test support includes:

- Notifying those users who have not logged on that the disaster system is up and ready for user testing,
- Responding to general user questions and to user problem reports, ensuring they are resolved, and
- Recording all problem reports and general notes to a system status database that is made available to users to read.

### **4.4 Post-Test Wrap-Up**

Two debriefings are schedule on the days immediately following the hot site test. One is for the HST Team participants to assess the systems software recovery procedures. The second is for the user community who participated in the HST.

These meetings are general discussions to address:

- Areas where the exercise was successful,
- Problems that were encountered, and
- Suggestions for improvements.

Based on the conclusions, an “action list” of improvements to be made prior to the next test is developed and responsibility for implementing them is assigned.

#### 4.5 Hot Site Test Schedule

The Data Center generally schedules two tests during a calendar year approximately six months apart. To date, eighteen tests have been conducted. The nineteenth hot site recovery exercise is scheduled for **Monday and Tuesday, July 19 - 20, 2004**. NIH has scheduled forty hours of test time for the mainframe and UNIX configurations starting at 8:00 a.m., Eastern time on the 8th.

The HST Team will have access to the systems on July 19, 2004 to restore the system/subsystem software and test the data communication link prior to the critical application users’ access on the following day.

The twentieth HST is scheduled for Monday and Tuesday, December 6 -7, 2004. The following are the dates of the previous tests for the indicated systems:

- HST1: May 3, 1994 – NIH mainframe
- HST2: March 21, 1995 – NIH mainframe
- HST3: September 12, 1995 – NIH mainframe
- HST4: March 14, 1996 – NIH mainframe
- HST5: October 22, 1996 – NIH mainframe
- HST6: May 13, 1997 – NIH mainframe
- HST7: December 12, 1997 – NIH mainframe
- HST8: July 21, 1998 – North and South (consolidation of NIH and HHS mainframes onto two LPARS at NIH)
- HST9: January 22, 1999 – North and South
- HST10A: June 7, 1999 – EOS
- HST10: August 30-31, 1999 – North, South, and EOS
- HST11: February 22-23, 2000 – North, South, and EOS
- HST12: August 14-15, 2000 – North, South, and EOS
- HST13: March 26 - 27, 2001 – North, South, Titan, and EOS
- HST14: November 01 –02, 2001 – Titan (standardized system to replace North and South; hosting North applications at the time of the test), South, and EOS
- HST15: March 26 – 27, 2002 – Titan, South, and EOS
- HST16: November 12 – 13, 2002 – Titan, South, and EOS
- HST17: July 21 – 22, 2003 – Titan, South, and EOS
- HST18: December 8 – 9, 2003 – Titan and EOS

## 4.6 Plan Reviews and Training

In addition to regular testing, periodic reviews of the various sections of the plan and training of disaster response participants ensure the total plan remains up to date, and disaster response participants remain cognizant of their functions. The following reviews and training have occurred:

<u>Date</u>	<u>Activity</u>
11/12/03	Review of alert procedures specified in Appendix C.

## 5 Maintaining the Plan

The Disaster Recovery Coordinator of the Data Center is responsible for the maintenance of this document. The plan is periodically updated:

- in response to events such as office moves, telephone number changes, new personnel joining DCSS, retirements, duty changes, and additions or deletions of designated critical applications;
- after each hot site test to reflect the recommendations resulting from the post-test wrap-up debriefings; and
- after a periodic review of the plan.

Additionally, the plan will be updated in the event an actual disaster occurs. The plan will be reviewed and updated at a convenient point after the initial responses to the disaster have been completed.

### ***Revision History:***

<b><u>Revision Date</u></b>	<b><u>Summary of Changes</u></b>
November, 2000:	The <i>Disaster Recovery Plan</i> , covering the mainframe systems and the <i>Compaq Digital AlphaServer Disaster Recovery Plan</i> were revised following the August, 2000 disaster recovery tests.
July, 2001:	Major restructuring and revision of the disaster recovery plan was completed. The prior two plans are now combined into one plan.
October, 2001	Revised Appendices B, C, D, G, and J due to changes in communications support and the Comdisco contract, and in preparation for the November, 2001 disaster recovery test.
November/December, 2001	Revised main body and Appendices A, C and F following the November, 2001 disaster recovery test.
March, 2002	Revised Appendix J for distribution to customers prior to March, 2002 disaster recovery test.
May 2002	Revised main body and Appendices A, B, C, D, F, G, H, J, K, and L due to contractual changes, customer responses to application surveys, and results of the March, 2002 disaster recovery test.
June, 2002	Revised Attachments list in table of contents to include Department of the Treasury instructions, and Appendices A, C, D, and, I due to further

responses to application surveys, contact information changes, and reviews of procedures.

October, 2002 Revised sections 1, 2, and 4 to reflect contractual changes; Appendix A to reflect changes in applications participating in the Disaster Recovery Program; Appendices B and D to reflect the new work area recovery location; Appendix C to change format and update contact telephone numbers; Appendix F to reflect updates to recovery procedures based upon further reviews; Appendix J in preparation for the November hot site test; and Appendix I to reflect the new location of the Information Security and Awareness Office.

August, 2003 Revised section 1 to clarify user responsibilities; section 4 to record recent test dates; Appendix A to reflect changes to applications supported; Appendix C to reflect personnel changes and to update telephone numbers; Appendix D to reflect changes in vendor support personnel and to update notification procedures; Appendix F to reflect changes to recovery procedures; Appendix G to reflect new IP addresses and update information regarding the T1 line; and Appendix J in preparation for the July hot site test.

April, 2004 Revised sections 1 and 2 to eliminate references to South which was decommissioned January 12, 2004; section 3 to reflect updates to team responsibilities; section 4 to record recent test dates and to describe plan review process and employee training; section 5 to indicate plan approvals; Appendix A to reflect changes to applications supported; Appendix C to reflect personnel changes and updates to alert procedures; Appendix D to reflect changes in vendor support personnel; Appendix F to reflect changes to recovery procedures; Appendix G to reflect changes to IP addresses and pending relocation of the T-1 line; Appendix J in preparation for the December hot site test. Eliminated Appendix L, Hot Site JCL (South) due to the decommissioning of South.

***Plan Approval:***

<b>Revision</b>	<b>Signed, Director DCSS</b>	<b>Date</b>
April, 2004	/s/ John Dickson	4/12/04